

RESEARCH ARTICLE

Open Access



Accuracy of pulse oximetry in detection of oxygen saturation in patients admitted to the intensive care unit of heart surgery: comparison of finger, toe, forehead and earlobe probes

Sohila Seifi¹, Alireza Khatony^{2*}, Gholamreza Moradi³, Alireza Abdi² and Farid Najafi⁴

Abstract

Background: Heart surgery patients are more at risk of poor peripheral perfusion, and peripheral capillary oxygen saturation (SpO₂) measurement is regular care for continuous analysis of blood oxygen saturation in these patients. With regard to controversial studies on accuracy of the current pulse oximetry probes and lack of data related to patients undergoing heart surgery, the present study was conducted to determine accuracy of pulse oximetry probes of finger, toe, forehead and earlobe in detection of oxygen saturation in patients admitted to intensive care units for coronary artery bypass surgery.

Methods: In this clinical trial, 67 patients were recruited based on convenience sampling method among those admitted to intensive care units for coronary artery bypass surgery. The SpO₂ value was measured using finger, toe, forehead and earlobe probes and then compared with the standard value of arterial oxygen saturation (SaO₂). Data were entered into STATA-11 software and analyzed using descriptive, inferential and Bland-Altman statistical analyses.

Results: Highest and lowest correlational mean values of SpO₂ and SaO₂ were related to finger and earlobe probes, respectively. The highest and lowest agreement of SpO₂ and SaO₂ were related to forehead and earlobe probes.

Conclusion: The SpO₂ of earlobe probes due to lesser mean difference, more limited confidence level and higher agreement ratio with SaO₂ resulted by arterial blood gas (ABG) analysis had higher accuracy. Thus, it is suggested to use earlobe probes in patients admitted to the intensive care unit for coronary artery bypass surgery.

Trial registration: Registration of this trial protocol has been approved in Iranian Registry of Clinical Trials at 2018–03-19 with reference [IRCT20100913004736N22](https://doi.org/10.1186/s12912-018-0283-1). "Retrospectively registered."

Keywords: Pulse oximetry, Critical care, Accuracy

Background

Pulse oximetry is a simple and non-invasive method used to examine oxygen saturation (SpO₂) in various parts of body [1]. Using pulse oximetry is effective in accelerating the weaning from mechanical ventilation and extubation and reduces the frequency of bleeding for analysis of arterial blood gases (ABG), because for the

patients who just need checking for the O₂ saturation, pulse oximetry could be a proper alternative [2, 3]. Convenient use, speed and high accuracy in detection of hypoxia and continuous monitoring of patients are other features of pulse oximetry [3–5]. This device detects the amount of oxyhemoglobin and deoxygenated hemoglobin in arterial blood and shows it as Oxyhemoglobin saturation (SpO₂) [6] which is an indirect estimation of arterial oxygen saturation (SaO₂) [7]. The normal amount of SpO₂ in healthy individuals is 97% to 99% [8].

* Correspondence: Akhatony@kums.ac.ir

²Nursing department, Nursing and Midwifery School, Kermanshah University of Medical Sciences, Kermanshah, Iran

Full list of author information is available at the end of the article



If the SaO₂ is 70% to 100%, the amount of SpO₂ has high accuracy and is 2% different from the SaO₂ amount obtained from ABG analysis [5]. Yet, in more critically ill patients, the amount of pulse oximetry error is reported as 7.2% [9]. Various factors can affect the accuracy of the device including the physiologic, environmental, technology failures and human error [1, 3, 7, 10–12].

There are contradictory and controversial results regarding the accurate detection of SpO₂ by pulse oximeter obtained from the related studies [13–16]. Nessler et al. (2012) in their study concluded that among the patients under vasopressors, the forehead pulse oximeter sensor had higher accuracy in detection of SpO₂ compared to transitional pulse oximetry of fingers [13]. The study of Bilan et al. (2006) indicated pulse oximetry by earlobe probe, had higher accuracy compared to pulse oximetry of finger and toe probes in detection of hypoxemia in children and babies. Further, it was shown that pulse oximetry of finger probes had the lowest agreement with SpO₂ [14]. Korhan et al. (2011) suggested that in patients under physical restraints, the unfolded finger should be used to show the accurate value of SpO₂ [15]. Wilson et al. (2010), in a retrospective cohort study, reported the difference of 2.7% between SpO₂ and SaO₂ in emergency patients with severe sepsis and septic shock and suggested using ABG where there is a need for more accurate detection of SaO₂ [1]; the authors suggested doing more investigations due to the limitations of the study such as insufficient sample size.

Sugino et al. (2004) compared the pulse oximetry of forehead and finger probes in patients under general anesthesia. For this purpose, eighteen patients were induced by Propofol and time of lowest, time to recovery and lag time of beginning of SpO₂ were measured for finger and forehead probes. The results showed that there are no differences between pulse oximetry of forehead and finger in terms of the mentioned times in a general anesthesia, and the authors suggested, the forehead probe can be a proper replacement when it is not possible to use finger probe [16]. Common methods such as forehead and finger probes have higher reliability in detection of peripheral oxygen saturation in patients with normal condition. However, these methods are not effective in critically ill patients hospitalized in intensive care unit with changes in vital signs because they have some limitations such as having edema in attached sites, and difficulties to matched control group [17, 18].

Considering the limitations and advantages of pulse oximetry in various parts of the body, the importance of accurate detection of hypoxemia and lack of studies about the proper method of pulse oximetry in patients admitted to intensive care units for coronary artery bypass surgery, the present study was conducted to determine the accuracy of pulse oximetry probes of finger,

toe, forehead and earlobe in detection of oxygen saturation in the patients admitted to the intensive care unit for coronary artery bypass surgery.

Methods

In this clinical trial, the study population was the patients admitted to the intensive care unit of Imam Ali (AS) Hospital affiliated to Kermanshah University of Medical Sciences (KUMS) for coronary artery bypass surgery. Study sample included 67 patients estimated based on the mean difference of 0.15 between measured SpO₂ of finger, toe and forehead probes in the study by Yunt et al. (2011) [12], test power of 90% and probability error of first type as 5%.

These patients were selected based on convenience sampling and the inclusion criteria included having arterial line, oral temperature above 35 °C, Hemoglobin greater than 9 g/dl, mean arterial pressure of higher than 60 mmHg, PaO₂ between 70% to 100% and pCO₂ less than 45 mmHg, lack of underlying problems such as blood disorders (for example anemia, methemoglobinemia, carboxyhemoglobinemia), left ventricular failure, peripheral vascular disease, and acute and chronic renal failure, not having nail polish and finger clubbing, no history of smoking, and lack of ulcers, burns, edema and dressing in probe placement. Patients whose mean arterial pressure reached less than 60 mmHg or needed suction, received medicines affecting vessel diameter and had change position, were excluded from the study.

Instrument

The portable probes of finger, toe and the forehead reflectance and earlobe pulse oximeter of Novametrx, Max-Fast, Nellcor Puritan Bennett INC, Pleasanton, Calif made in USA were used regarding all the patients for measurement of SpO₂ values, respectively. In addition, four similar portable monitoring OXYPLETH 520A devices made in USA were used. The ABG reader XHOP SPLUL device made in USA was used in order to measure the ABG. Tympanic thermometer Jinus (series stat profile PHOX) was also used for measuring the temperature. In order to determine the reliability of ABG device which is considered as the standard of the study, two sample of arterial blood of 2 cm³ were taken from one of the patients. One of the samples was sent to the laboratory and the second sample was put in refrigerator after bleeding. The second sample was sent to the laboratory in a time interval of two minutes following the first sample. Results of the study showed that there was an error of 0.11 between the SaO₂ of both samples which showed the high reliability of the device.

Three blood samples of 2 cm³ were taken from one of the patients in order to determine the reliability of the ABG device. One of the samples was analyzed using the ABG reader device of the study and the other two

Table 1 Comparing the correlation and agreement of SpO₂ of four probes with standardized SaO₂

Statistical index	Correlation			Agreement	
	r	p	CI	Rho	CI 95%
Finger	0.76	< 0.001	-1.02-2.08	0.68	-0.80- 0.57
Toe	0.60	< 0.001	-1.69- 2.28	0.58	-0.74- 0.43
Earlobe	0.77	< 0.001	-1.54- 1.83	0.76	-0.87- 0.67
Forehead	0.73	< 0.001	-1.07- 3.58	0.50	-0.62- 0.38

samples were analyzed using another ABG reader device. Results of the study showed that there was a correlation of 0.93 between the SaO₂ obtained from three ABG reader devices which indicated high correlation and reliability of the device. Four monitoring devices were of a same type and calibrated before the study. Tympanic thermometer was also calibrated prior to be used.

Data collection

In order to collect the data, permission to conduct the study was issued by the Ethical Committee of KUMS. Then the required permissions were taken from Deputy of Research and Technology of KUMS and provided to the officials of the Imam Ali Hospital. Then, the researcher referred to the intensive care unit of the hospital every day and invited the patients having inclusion criteria. For this purpose, first of all the research purpose was explained to the patients and if they wished to be included in the study, they were asked to sign a written informed consent. The patients were assured about the anonymity and confidentiality of personal information. First of all, a blood sample 2 cm³ was taken from each patients through artery catheter by the researcher. Then the samples were put inside an ice container and immediately sent to the laboratory next to the ICU. Hb (Hemoglobin) and temperature of the patients were also recorded in the ABG test. Tympanic thermometer was used in order to measure the patients' temperature. Further, the ratio and duration of SpO₂ was also measured at the same time using the finger, toe, earlobe and forehead probes. It should also be mentioned that the same probes were used for all the patients.

Devices were calibrated prior to using the pulse oximetry. All the patients were in supine position and while the bed was 30 degrees above body surface area. A cover

was put around the probes in order to prevent the intervention of environmental light with the performance of each four pulse oximetry probes. Moreover, unnecessary actions such as changing the position, suction, and medication were avoided while using probes to prevent any change in hemodynamic condition of the patients. SpO₂ value showed on the monitor in finger, toe, earlobe and forehead probes were measured and recorded at the same time per 60 s for 5 min in time intervals of 0, 1,2,3,4 and 5 min. Finally, the mean SpO₂ was calculated for each probe. The SpO₂ values of each probe and also the SaO₂ values were recorded on the information sheet.

Data analysis

Data were analyzed using STATA-11 software. Independent t-test, Pearson correlation coefficient and Rho coefficient were used to compare the SpO₂ and SaO₂ of four probes. Bland- Altman analysis was used to compare the accuracy of each pulse oximetry probes. Lesser mean difference and higher agreement indicated higher accuracy of the probe. Kappa coefficient was used in order to divide the agreement ratio with the range of 0–1. Closer amounts indicate higher agreement [19].

Results

Of the 67 patients, 56.7% (*n* = 38) were female and 43.3% (*n* = 29) were male. The mean and standard deviation of patients' age were 57.22 ± 13.71 years. The mean and standard deviation of sample Hb was estimated as 13.21 ± 2.01 g/dl. The mean PaO₂ in 43.3% of the sample was about 70–70.9 mmHg. The mean and standard deviation of the samples' temperature were and 36.8 ± 0.6 °C and 58.2% of the sample had the temperature of 36–36.9 °C. The mean and standard deviation of PaCO₂ were 35.03 ± 5.57 mmHg and this values for PaO₂ were 96.81 ± 1.20%.

Table 2 agreement and mean difference of Finger, Toe, Earlobe and Forehead pulse oximeters comparing to Standard SaO₂

Statistical index	Mean	SD	Mean difference SaO ₂ -SpO ₂	p-Value for t-test of mean difference	CI 95% for agreement
SpO ₂ probe					
Forehead	95.55	1.75	1.25 ± 1.18	< 0.001	0.38–0.62
Earlobe	96.67	1.34	0.14 ± 0.86	0.019	0.67–0.87
Finger	96.28	1.06	0.53 ± 0.79	< 0.001	0.57–0.80
Toe	96.52	1.06	0.29 ± 1.01	0.22	0.43–0.74




Fig. 1 Bland-Altman plot of earlobe for measuring SpO2

Based on the Pearson correlation test, the highest and lowest correlation between the mean SpO2 and mean SaO2 were related to earlobe probe ($r = 0.77, P < 0.001$) and toe probe ($r = 0.60, P < 0.001$). The highest and lowest clinical agreement with standard SaO2 were related to earlobe probes (0.76) and forehead probes (0.50), respectively. The confidence level (CI) calculated for clinical agreement in earlobe probe was less than other probes (Table 1).

The lowest mean difference of SpO2 or SaO2 was related to earlobe probe (0.14 ± 0.86) and the highest difference ratio was related to forehead probe (1.25 ± 1.18) (Table 2).

Figures 1, 2, 3 and 4 show the Bland-Altman plot of comparing the clinical agreement between SaO2 or SpO2 values of earlobe, toe, forehead and finger probes where the earlobe probe with the agreement of 0.76 and confidence interval of 1.54–1.83 had the highest agreement with SaO2.

Discussion

In this study, the earlobe probes had the highest clinical agreement with SaO2 and higher accuracy due to less mean difference and limited confidence interval following by the finger, toe and forehead probes. Results of the study by Bilan et al. (2010) indicated pulse oximetry of




Fig. 2 Bland-Altman plot of forehead for measuring SpO2




Fig. 3 Bland-Altman plot of toe for measuring SpO2

earlobe probe had higher accuracy compared to pulse oximetry of finger and toe probes in detection of hypoxemia in children and babies. Further, it was shown that pulse oximetry of finger probe had the lowest agreement with SaO2 [4]. However, Vax et al. (2009) compared the ear and forehead probes in patients under coronary surgery and reported that forehead probe had higher clinical agreement compared to ear probe [20]. Benz et al. (1991) also examined the accuracy of Biox 3700 pulse oximeter in patients receiving medicines affecting vessel diameter and reported that the ear probe of patients receiving medicines affecting vessel diameter was not

reliable for monitoring SaO2 [21]. It seems that measuring the oxygen saturation using pulse oximeter can be influenced by the patient's condition; in this regard, Eberhard et al. (2002) stated that earlobe probe was the proper method in patients under anesthesia due to high speed of detecting SaO2 [22]. Lindholm et al. (2007) also argued that earlobe probe was the more proper method compared to finger probe due to more sensitivity to peripheral hypoxia in detection of SaO2 in patients with apnea [23]. Simon et al. (2003) also showed that ear probe was a more proper approach compared to finger probe in hypothermia [24].




Fig. 4 Bland-Altman plot of finger for measuring SpO2

However, other studies had different results based on patients' condition [7, 25–27]. In this regard, Fernandez et al. (2007), in a method-comparison study, assessed the agreement between SpO₂ values by digit-based and forehead pulse oximeters in low cardiac index patients, they suggested using forehead probe in these patients since the peripheral blood flow and body temperature are decreased [25]. Schallom et al. also claimed that in critically ill patients under surgery or with trauma exposed to the risk of peripheral hypoperfusion, the SpO₂ ratio by forehead probe was more accurate than finger probe [26]. Das et al. (2010) also believe that there is no proper method for the placement of pulse oximeter sensor in children with cyanotic heart disease due to their specific condition to show the accurate value of SpO₂. However, foot sensor can be the more appropriate one in this regard [7]. Sedaghat Yazdi et al. (2008) examined the effect of placement on the accuracy and reliability of the pulse oximeter sensor in children with cyanotic heart disease and found that if the SaO₂ ≤ 90%, the foot sensor had the worst accuracy and reliability. Further, regardless of SaO₂ amount, there was no difference between finger and toe sensor in terms of accuracy and reliability [27].

Although the accuracy of pulse oximetry is reduced in patients with severe and rapid O₂ desaturation, low blood pressure, body temperature, dyshemoglobinemia and reduced blood perfusion conditions [28], the earlobe pulse oximetry had more accurate and reliable performance regarding these changes [22, 23, 29]. Haynes (2007) claimed that earlobe probe can be considered as the proper method of finger pulse oximetry since in finger probe, the body movement is limited and the risk of reduced tissue perfusion is increased [18]. Thus, regarding the importance of continuous monitoring and maintaining hemodynamic stability in patients under heart surgery [29] and considering the results of our study, the earlobe probe can be used as the proper method for examining the oxygen saturation in patients under heart surgery.

In this study, the environmental light could intervene with the performance of each four pulse oximetry probes. However, a cover was put around the probes in order to prevent the intervention of environmental light with the performance of each four pulse oximetry probes. Non-random sampling was used for this study which could affect the generalizability of the findings. Thus, it is suggested to replicate the study using random sampling in various patients. The study was conducted on the patients admitted to the intensive care unit for cardiac surgery and it is suggested to conduct the similar study on the patients admitted to emergency and operating rooms.

Conclusion

Results of the study indicated that earlobe probe had higher accuracy in showing the SpO₂ among patients admitted to

the intensive care unit for heart surgery compared to finger, toe and forehead probes and the obtained SpO₂ value of earlobe probe approximated to the SaO₂ obtained from ABG test. Thus, earlobe probe can be used in intensive care units to measure the peripheral oxygen saturation.

Abbreviations

ABG: Arterial Blood Gases; C: Centigrade; Hg: hemoglobin; KUMS: Kermanshah University of Medical Sciences; Sao₂: Saturation of Oxygen (arterial blood); Spo₂: Spot Oxygen Saturation

Acknowledgements

This work was performed in partial fulfillment of the requirements for MSc. degree of Soheila Seifi, in faculty of nursing and midwifery, Kermanshah University of Medical Sciences, Kermanshah, Iran. This article was drawn from a research project (No. 90099) sponsored by deputy of research and technology of KUMS. We appreciate **Clinical research development Unit of Imam Reza Hospital** and patients who contributed to the study.

Funding

This study was drawn from a research project (No. 90099) sponsored by deputy of research and technology of KUMS. The cost of the payment is spent on the design and implementation of the study.

Availability of data and materials

Data available by contacting the corresponding author.

Authors' contributions

SS, AK, GM, FN and AA contributed in designing the study, SS, AK and GM collected the data, and analyzed by FN and AA. The final report and article were written by SS, AK, FN, and AA and they were read and approved by all the authors.

Ethics approval and consent to participate

The study was approved by ethics committee of Kermanshah University of Medical Sciences with reference number ir.kums.rec.1396.710. Written consent was obtained from participants.

Consent for publication

Not applicable

Competing interests

The authors declare there are no competing interests.

Publisher's Note

Springer Nature remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.

Author details

¹Students Research Committee, Kermanshah University of Medical Sciences, Kermanshah, Iran. ²Nursing department, Nursing and Midwifery School, Kermanshah University of Medical Sciences, Kermanshah, Iran. ³Department of anesthesiology, Medicine School, Kermanshah University of Medical Sciences, Kermanshah, Iran. ⁴Research Center for Environmental Determinants of Health (RCEDH), School of Public Health, Kermanshah University of Medical Sciences, Kermanshah, Iran.

Received: 20 March 2017 Accepted: 21 March 2018

Published online: 17 April 2018

References

- Wilson BJ, Cowan HJ, Lord JA, Zuege DJ, Zygun DA. The accuracy of pulse oximetry in emergency department patients with severe sepsis and septic shock: a retrospective cohort study. *BMC emergency medicine*. 2010;10(1):1.
- Niknafs P, Norouzi E, Bijari BB, Baneshi MR. Can we replace arterial blood gas analysis by pulse oximetry in neonates with respiratory distress syndrome, who are treated according to INSURE protocol? *Iranian journal of medical sciences*. 2015;40(3):264.

3. Berkenbosch JW, Tobias JD. Comparison of a new forehead reflectance pulse oximeter sensor with a conventional digit sensor in pediatric patients. *Respir Care*. 2006;51(7):726–31.
4. Bilan N, Behbahan AG, Abdinia B, Mahallei M. Validity of pulse oximetry in detection of hypoxaemia in children: comparison of ear, thumb and toe probe placements/Validité de l'oxymétrie de pouls pour détecter l'hypoxémie chez l'enfant: comparaison du placement de la sonde au niveau de l'oreille, du pouce et de l'orteil. *East Mediterr Health J*. 2010;16(2):218.
5. Pluddemann A, Thompson M, Heneghan C, Price C. Pulse oximetry in primary care: primary care diagnostic technology update. *Br J Gen Pract*. 2011;61(586):358–9.
6. Ruskin KJ, Wagner JL. Pulse oximetry: basic principles and applications in aerospace medicine. *Aviat Space Environ Med*. 2008;79(4):444.
7. Das J, Aggarwal A, Aggarwal NK. Pulse oximeter accuracy and precision at five different sensor locations in infants and children with cyanotic heart disease. *Indian journal of anaesthesia*. 2010;54(6):531.
8. Schutz SL. Oxygen saturation monitoring by pulse oximetry. *AACN procedure manual for crit care*. 2001;4:77–82.
9. Durbin CG Jr, Rostow SK. More reliable oximetry reduces the frequency of arterial blood gas analyses and hastens oxygen weaning after cardiac surgery: a prospective, randomized trial of the clinical impact of a new technology. *Crit Care Med*. 2002;30(8):1735–40.
10. Blaylock V, Brinkman M, Carver S, McLain P, Matteson S, Newland P, et al. Comparison of finger and forehead oximetry sensors in postanesthesia care patients. *J Perianesth Nurs*. 2008;23(6):379–86.
11. Hodgson CL, Tuxen DV, Holland AE, Keating JL. Comparison of forehead max-fast pulse oximetry sensor with finger sensor at high positive end-expiratory pressure in adult patients with acute respiratory distress syndrome. *Anaesth Intensive Care*. 2009;37(6):953.
12. GHl Y, Korhan EA, Khorshid L. Comparison of oxygen saturation values and measurement times by pulse oximetry in various parts of the body. *Appl Nurs Res*. 2011;24(4):e39–43.
13. Nessler N, Fmel JV, Launey Y, Morcet J, Malldant Y, Seguin P. Pulse oximetry and high-dose vasopressors: a comparison between forehead reflectance and finger transmission sensors. *Intensive Care Med*. 2012;38(10):1718–22.
14. Bilan N, ABDI NB, Mahallei M. Validity of pulse oximetry of earlobe, toe and finger in the detection of pediatric hypoxemia. 2006.
15. Korhan EA, Yont GH, Khorshid L. Comparison of oxygen saturation values obtained from fingers on physically restrained or unrestrained sides of the body. *Clinical Nurse Specialist*. 2011;25(2):71–4.
16. Sugino S, Kanaya N, Mizuuchi M, Nakayama M, Namiki A. Forehead is as sensitive as finger pulse oximetry during general anesthesia. *Can J Anesth*. 2004;51(5):432–6.
17. Cheng EY, Hopwood MB, Kay J. Forehead pulse oximetry compared with finger pulse oximetry and arterial blood gas measurement. *J Clin Monit*. 1988;4(3):223–6.
18. Haynes JM. The ear as an alternative site for a pulse oximeter finger clip sensor. *Respir Care*. 2007;52(6):727–9.
19. Viera AJ, Garrett JM. Understanding interobserver agreement: the kappa statistic. *Fam Med*. 2005;37(5):360–3.
20. Wax DB, Rubin P, Neustein S. A comparison of transmittance and reflectance pulse oximetry during vascular surgery. *Anesth Analg*. 2009;109(6):1847–9.
21. Ibanez J, Velasco J, Raurich JM. The accuracy of the biox 3700 pulse oximeter in patients receiving vasoactive therapy. *Intensive Care Med*. 1991;17(8):484–6.
22. Eberhard P, Gisiger PA, Gardaz JP, Spahn DR. Combining transcutaneous blood gas measurement and pulse oximetry. *Anesth Analg*. 2002;94(1 Suppl):S76–80.
23. Lindholm P, Blogg SL, Gennser M. Pulse oximetry to detect hypoxemia during apnea: comparison of finger and ear probes. *Aviat Space Environ Med*. 2007;78(8):770–3.
24. Simon SB, Clark RA. (Mis) using pulse oximetry: a review of pulse oximetry use in acute care medical wards. *Clin Eff Nurs*. 2002;6(3):106–10.
25. Fernandez M, Burns K, Calhoun B, George S, Martin B, Weaver C. Evaluation of a new pulse oximeter sensor. *Am J Crit Care*. 2007;16(2):146–52.
26. Schallom L, Sona C, McSweeney M, Mazuski J. Comparison of forehead and digit oximetry in surgical/trauma patients at risk for decreased peripheral perfusion. *Heart & Lung: The Journal of Acute and Critical Care*. 2007;36(3):188–94.
27. Sedaghat-Yazdi F, Torres A Jr, Fortuna R, Geiss DM. Pulse oximeter accuracy and precision affected by sensor location in cyanotic children. *Pediatr Crit Care Med*. 2008;9(4):393–7.
28. Jensen LA, Onyskiw JE, Prasad NGN. Meta-analysis of arterial oxygen saturation monitoring by pulse oximetry in adults. *Heart & Lung: The Journal of Acute and Critical Care*. 1998;27(6):387–408.
29. Westphal GA, Silva E, Gonçalves AR, Caldeira Filho M, Poli-de-Figueiredo LF. Pulse oximetry wave variation as a noninvasive tool to assess volume status in cardiac surgery. *Clinics*. 2009 Apr;64(4):337–43.

Submit your next manuscript to BioMed Central and we will help you at every step:

- We accept pre-submission inquiries
- Our selector tool helps you to find the most relevant journal
- We provide round the clock customer support
- Convenient online submission
- Thorough peer review
- Inclusion in PubMed and all major indexing services
- Maximum visibility for your research

Submit your manuscript at
www.biomedcentral.com/submit

